

Tabela robót ziemnych										
DG 332079P ul. Drukarska 2									Tabela 2.1	
PIKIETAŻ	POWIERZCHNIA		OBJĘTOŚCI			ZUŻYCIE NA MIEJSCU	NADMIAR OBJ,		SUMA	
	WYKOP	NASYP	ODL,	WYKOP	NASYP		WYKOP	NASYP	+	-
km	m ²	m ²	m	m ³	m ³	m ³	m ³	m ³	m ³	m ³
0+003,50	1,20	1,90	50,50	60,60	95,95	60,60	0,00	-35,35	0,00	0,00
0+054,00	1,20	1,90								-35,35
			14,00	20,30	21,70	20,30	0,00	-1,40		
0+068,00	1,70	1,20	7,00	11,90	8,40	8,40	3,50	0,00		-36,75
0+075,00	1,70	1,20							-33,25	
			SUMA	92,80	126,05	89,30	3,50	-36,75		

KM	WYK	NAS
3,5	1,20	1,90
54,00	1,20	1,90
68,00	1,70	1,20
75	1,70	1,20

		WYKOP	NASYP
+10%	SUMA	102,08	138,66