

Nazwa elementu	Symbol elem.	Przekrój	Długość elem.	elem. w kons.	suma mb	KUBATURA POSZCZ. PRZEKROJÓW							
						10x16	2,5x25	4x8	8x16	16x16	14x14	5x16	5x12
						0,10	0,025	0,04	0,08	0,16	0,14	0,05	0,05
						0,16	0,20	0,08	0,16	0,16	0,14	0,16	0,12
		(cm)	(m)	(szt.)	(mb)	(m3)	(m3)	(m3)	(m3)	(m3)	(m3)	(m3)	(m3)
Krokwie dach spadzisty	K1	8x16	9,75	16	156,00				1,997				
	K2	8x16	0,96	2	1,92				0,025				
	K3	8x16	1,90	2	3,80				0,049				
	K4	8x16	2,80	2	5,60				0,072				
	K5	8x16	3,74	2	7,48				0,096				
	K6	8x16	4,65	2	9,30				0,119				
	K7	8x16	5,60	2	11,20				0,143				
	K8	8x16	6,50	2	13,00				0,166				
	K9	8x16	7,43	2	14,86				0,190				
	K10	8x16	8,46	2	16,92				0,217				
	K11	8x16	9,20	20	184,00				2,355				
	K12	8x16	3,83	1	3,83				0,049				
	K13	8x16	4,32	1	4,32				0,055				
	K14	8x16	13,05	8	104,40				1,336				
	K15	8x16	8,90	3	26,70				0,342				
	K16	8x16	11,21	8	89,68				1,148				
	K17	8x16	2,45	1	2,45				0,031				
	K18	8x16	7,24	1	7,24				0,093				
	K19	8x16	2,34	1	2,34				0,030				
	K20	8x16	6,77	2	13,54				0,173				
	K21	8x16	3,37	1	3,37				0,043				
	K22	8x16	5,83	2	11,66				0,149				
	K23	8x16	2,36	10	23,60				0,302				
	K24	8x16	1,98	2	3,96				0,051				
	K25	8x16	1,05	2	2,10				0,027				
	K26	8x16	4,53	14	63,42				0,812				
	K27	8x16	3,18	2	6,36				0,081				
	K28	8x16	2,23	2	4,46				0,057				
	K29	8x16	1,30	2	2,60				0,033				
	K30	8x16	2,75	1	2,75				0,035				
	K31	8x16	2,92	75	219,00				2,803				
	K32	8x16	4,15	16	66,40				0,850				
	K33	8x16	3,15	2	6,30				0,081				
Krokiew	KN1	10x16	12,63	1	12,63	0,202							
Narożna	KN2	10x16	3,38	2	6,76	0,108							
	KN3	10x16	5,53	2	11,06	0,177							
Murłata	MU1	16x16	6,57	2	13,14				0,336				
	MU2	16x16	6,29	1	6,29				0,161				
	MU3	16x16	22,64	1	22,64				0,580				
	MU4	16x16	6,60	4	26,40				0,676				
	MU5	16x16	5,40	2	10,80				0,276				
	MU6	16x16	36,36	2	72,72				1,862				
	MU7	16x16	5,86	1	5,86				0,150				
	MU8	16x16	1,95	1	1,95				0,050				
Płatew	PŁ1	16x16	6,57	2	13,14				0,336				
	PŁ2	16x16	2,96	1	2,96				0,076				
	PŁ3	16x16	9,60	1	9,60				0,246				
	PŁ4	16x16	9,35	1	9,35				0,239				
	PŁ5	16x16	1,75	1	1,75				0,045				
	PŁ6	16x16	1,59	1	1,59				0,041				
	PŁ7	16x16	2,41	2	4,82				0,123				
	PŁ8	16x16	5,97	1	5,97				0,153				
	PŁ9	16x16	4,35	2	8,70				0,223				
	PŁ10	16x16	4,22	2	8,44				0,216				
	PŁ11	16x16	6,17	1	6,17				0,158				
	PŁ12	16x16	16,50	1	16,50				0,422				
Podwalina	PD2	16x16	2,96	1	2,96				0,076				
	PD3	16x16	9,60	1	9,60				0,246				
	PD4	16x16	9,35	1	9,35				0,239				
	PD5	16x16	1,75	1	1,75				0,045				
	PD6	16x16	1,59	1	1,59				0,041				

	PD7	16x16	2,41	2	4,82					0,123			
	PD8	16x16	5,97	1	5,97					0,153			
	PD9	16x16	4,35	2	8,70					0,223			
	PD10	16x16	4,22	2	8,44					0,216			
	PD11	16x16	6,17	1	6,17					0,158			
	PD12	16x16	16,50	1	16,50					0,422			
Kleszcze	KL1	5x16	8,08	16	129,28							1,034	
	KL2	5x16	3,88	40	155,20							1,242	
	KL3	5x16	8,28	20	165,60							1,325	
	KL4	5x16	4,32	14	60,48							0,484	
	KL5	5x16	3,78	18	68,04							0,544	
	KL6	5x16	1,75	70	122,50							0,980	
	KL7	5x16	3,63	12	43,56							0,348	
Wymian	W1	8x16	0,88	12	10,56				0,135				
	W2	8x16	1,21	2	2,42				0,031				
	W3	8x16	0,79	2	1,58				0,020				
	W4	8x16	1,52	2	3,04				0,039				
	W5	8x16	2,04	2	4,08				0,052				
	W6	8x16	1,47	2	2,94				0,038				
Słupy	S1	16x16	4,49	2	8,98					0,230			
	S2	16x16	2,15	7	15,05					0,385			
	S3	16x16	1,73	6	10,38					0,266			
	S4	16x16	3,62	10	36,20					0,927			
Spinki	SP1	8X16	1,41	8	11,28				0,144				
Wieszaki	W1	5X16	2,31	16	36,96							0,296	
Deska okap.		2,5x25	200,00	1	200,00		1,000						
Razem				m3	0,487	1,000	0,000	14,470	10,118	0,000	6,253	0,000	
Ogółem				m3	32,328								