

TABELA RÓBÓT ZIEMNYCH
dla zadania pn :
Rozbudowa drogi powiatowej nr 1918G Wygoda
Łączyńska-Chmielno na odcinku Chmielno-Lipowiec

BILANS ROBÓT ZIEMNYCH - Dł. drogi							
Pikietaż	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu	Obj. netto
0+000.00	8.74	0.06	0.00	0.00	0.00	0.00	0.00
0+050.00	2.42	0.17	282.15	5.94	282.15	5.94	276.21
0+100.00	1.39	0.59	94.43	19.63	376.58	25.57	351.01
0+150.00	0.41	1.66	45.11	56.10	421.69	81.67	340.02
0+200.00	9.26	0.02	239.26	42.09	660.95	123.75	537.20
0+261.24	8.00	0.00	530.01	0.69	1190.96	124.44	1066.52
0+300.00	15.86	0.00	456.30	0.00	1647.26	124.44	1522.82
0+350.00	7.17	0.00	571.88	0.00	2219.14	124.44	2094.70
0+400.00	16.62	0.00	594.17	0.00	2813.31	124.44	2688.87
0+450.00	3.06	0.81	491.46	19.93	3304.77	144.37	3160.40
0+500.00	4.78	2.04	199.12	70.21	3503.90	214.59	3289.31
0+550.00	3.05	4.04	195.78	151.87	3699.68	366.46	3333.22
0+566.00	1.85	3.28	38.92	58.84	3738.60	425.30	3313.29
0+600.00	4.37	3.08	102.98	109.90	3841.58	535.20	3306.37
0+650.00	8.57	0.59	316.63	93.87	4158.21	629.07	3529.14
0+700.00	2.42	0.14	274.34	18.44	4432.55	647.51	3785.04
0+750.00	2.10	0.00	113.68	3.49	4546.22	651.00	3895.22
0+800.00	0.35	1.82	61.83	45.25	4608.05	696.25	3911.80
0+850.00	1.26	1.75	40.80	88.47	4648.85	784.73	3864.13
0+900.00	12.42	2.26	345.11	98.97	4993.96	883.70	4110.27
0+950.00	11.93	0.63	608.93	72.25	5602.89	955.95	4646.94
1+000.00	25.56	0.00	943.66	15.62	6546.55	971.57	5574.98
1+050.00	26.62	0.03	1304.40	0.84	7850.95	972.40	6878.55
1+100.00	6.20	0.38	816.38	10.45	8667.33	982.86	7684.47
1+150.00	10.82	0.01	415.43	9.97	9082.76	992.83	8089.93
1+200.00	11.48	2.95	544.07	77.41	9626.83	1070.24	8556.59
1+250.00	22.54	0.00	824.33	76.40	10451.16	1146.64	9304.53
1+300.00	12.56	1.50	877.50	37.41	11328.66	1184.04	10144.62
1+350.00	3.10	1.80	397.98	81.38	11726.64	1265.42	10461.22
1+400.00	4.00	1.22	177.81	75.50	11904.45	1340.93	10563.52
1+450.00	7.85	0.68	293.28	48.13	12197.73	1389.05	10808.67
1+500.00	10.98	1.22	463.01	48.21	12660.74	1437.27	11223.48
1+550.00	7.26	0.40	449.81	41.14	13110.55	1478.41	11632.14
1+600.00	2.41	0.39	239.91	20.01	13350.45	1498.41	11852.04
1+650.00	18.95	0.34	528.48	18.29	13878.93	1516.70	12362.23
1+700.00	0.65	6.34	484.46	168.35	14363.39	1685.06	12678.33
1+750.00	0.00	34.76	16.02	1037.43	14379.41	2722.49	11656.92
1+800.00	0.00	14.55	0.00	1239.97	14379.41	3962.46	10416.95
1+850.00	3.24	3.76	85.00	441.89	14464.41	4404.35	10060.07
1+890.00	1.28	8.16	97.14	224.58	14561.55	4628.92	9932.63
1+950.00	1.07	30.62	71.14	1154.52	14632.69	5783.45	8849.24
2+000.00	5.51	5.88	158.44	936.79	14791.14	6720.24	8070.90
2+050.00	20.20	0.21	622.83	154.13	15413.97	6874.37	8539.60
2+100.00	6.60	0.27	669.97	12.15	16083.94	6886.52	9197.42
2+150.00	9.26	0.19	396.57	11.56	16480.50	6898.08	9582.43
2+200.00	4.92	1.22	354.65	35.20	16835.15	6933.28	9901.87
2+250.00	6.15	1.22	281.02	60.05	17116.17	6993.33	10122.85
2+300.00	5.39	0.89	287.35	52.99	17403.53	7046.32	10357.21
2+334.47	5.05	0.04	176.71	16.46	17580.23	7062.78	10517.45